BRUHAT BANGALORE MAHANAGARA PALIKE, BYATARAYAPURA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92
T.N. No. : 02/2010-11 Dated : 21.01.2011

DRAFT TENDR SCHEDULE-B

Issued to :

Original / Duplicate
Item No.

Name of Work: Improvements of Concrete Roads and Drains at Byatarayanapura in Ward No. 7, Kodigehalli Sub Division.

Sl. No.	Approved Quantity	Description	Unit	Sanctioned Rates	Rates Quoted by the Contractor	
				In Figures	In Figures	In Words
1	216.00	Removing B.S.Slab drain and stacking **(Page No. 24 & Item No. 5.32)**	Sqm	42.77		
2	348.30	KSRRB 300-1.1 : Earthwork excavation by manual means in **hard soil** involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. Specification No.KRBS 300-1 MORT & H Specification No.301 to 305 **(Page No. 126, Item No.19.1)**	Cum	129.60		
3	151.20	Refixing stone slabs of drains and pointing in C.M. (1:3) **(Page No. 24 & Item No. 5.33)**	Sqm	51.30		
4	64.80	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete **do 10 cms** thick	Sqm	304.56		
5	116.36	KSRRB 2900-4.1: Providing and laying in position **plain cement concrete mix 1:4:8** with stone aggregate 40mm and down size in foundation upto a depth of 2m below ground level and upto a height of 1.5m above ground level / bed level machine mixed, concrete laid in layers not exceeding 15cms thick well compacted, cost of all materials, labour, HOM of machineries, curing complete as per specifications. **(Page.12 & Item No. 4.3)**	Cum	3349.08		
6	106.55	KSRB 4-1.5 : Providing and laying in position **plain cement concrete** of mix **1:1.5:3** using 20mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 **(Page No. 12 & Item No. 4.11).**	Cum	4833.00		

7	27.78	KSRB 4.2.2 : Providing and laying in position **reinforced cement concrete** of mix **1:1.5:3** with 20mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1, 4.6. **(Page No. 12 & Item No. 4.11)**	Cum	4902.12			
8	19.45	KSRB 4.9.2 : Providing **T.M.T. Steel reinforcement for R.C.C.** work including straightening, cutting, bending, hooking , placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3. **(Page No. 16 & Item No. 4.46)**	Qtl	5204.52			
9	261.60	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2	Sqm	199.80			
10	348.30	Lead for disposal of debris shall be payable at Carriage rates by mechanical means with all lead and lift, loading, undloading and labour charges etc.,complete and as per the directions of the Engineer-in-charge of the work.	Cum				

I am prepared to execute the above mentioned work written by me in Schedule - B

Signature of the Contractor
Reg. No.
Postal Address

"DTS APPROVED"

Superintendent Engineer (T)
B.B.M.P.

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92